



SL-1750

Details & Installation Guide

October 2013

All information, descriptions and dimensions in this manual are current at the time of printing. As always, Custom-Bilt Metals in an effort to improve our product line reserves the right to make changes with products, details or designs, as necessary without notice and incurring no obligation. Please contact your local Custom-Bilt Metals Sales Representative for the most current information or visit our website at www.custombiltmetals.com



Table of Contents

SECTION	PAGE
Designer / Installer Notes	1
SL 1 Eave Detail	2
SL 2 Eave / Alt. Detail	3
SL 4 Eave - w/gutter Detail	4
SL 5 Eave - w/fascia Detail	5
SL 6 Ridge / Hip Detail	6
SL 7 Vented Ridge Detail	7
SL 8 Peak Detail	8
SL 9 Valley / thru fasten Detail	9
SL 10 Valley - w/cleat Detail	10
SL 11 Rake Detail	11
SL 12 Sidewall Detail	12
SL 13 Headwall Detail	13
SL 14 Headwall Detail	14
SL 15 Headwall / Vented	15
SL 16 Transition	16
SL 20 Pipe Penetration Detail	17
SL 22 Eave / Isometric Detail	18
SL 23 Valley / Isometric Detail	19
SL 24 Ridge / Hip Isometric Detail	20
SL 25 Zee Closure Detail	21
SL 25a Zee Closure end view Detail	22
SL 26 Curb Detail	23
SL 26a Curb / section Detail	24
SL 26b Curb / section Detail	25
SL 26c Curb / section Detail	26
SL 27 Panel Lap Detail	27



Designer/Installer Notes

GENERAL

Custom-Bilt Metals (herein as CBM) is providing the following installation instructions and details as a guideline, and are CBM's recommended procedures. All local building codes and project specifications should be followed, however, in all cases, good roofing practices, and good workmanship should be employed when constructing a roofing system using CBM's products. These procedures and details are not intended to cover all instances, building requirements, designs, or codes. These details may require changes or revisions for each project, as conditions vary from project to project. The details provided are proven methods of construction. Work shall be performed by experienced craftsmen familiar with metal roofing products and current industry standards. Sheet Metal and Air Conditioning Contractors National Association (SMACNA) architectural sheet metal manual shall govern material and workmanship not shown. Prefinished metals should not be required to have soldered joints because of expense and possible warranty violations by removing the coating system at the joint. Other joint designs and high quality sealants, gaskets and tapes are available and are recommended for prefinished metals. Note; Zincolume material cannot be soldered.

METAL ROOF SYSTEM

CBM's roof systems may be fabricated using Zincolume, G-90 galvanized steel, copper or aluminum. Various gauges are available; contact a CBM sales representative for details. The steel and aluminum panels are available prefinished in a full 70% PVDF (Polyvinylidene fluoride) or Kynar 500® or Hylar® 5000 or Fluropon® paint system. Bare Zincolume (Zincolume Plus) is also available. The paint system consists of a baked-on epoxy primer (.2 mil.) and a baked-on PVDF finish coat (.8 mil.) totaling a nominal 1.0 mil. dry film thickness. All flashing and trim (unless requested otherwise) are of the same gauge and finish as the roof panels. Refer to your project specifications for actual requirements. Note; high build paint systems are available and may be required for salt water environments.

SEALANTS

Sealants not exposed to direct sunlight should consist of either an elastic butyl rubber tape or a non-skinning, non-drying gun-able butyl. Single part polyurethane's should be used when exposed to ultraviolet light. All sealants should be applied to clean, dry surfaces to ensure weather tightness. Sealants shall be installed as shown without voids.

SUBSTRATE

CBM recommends a solid substrate (15/32" plywood, APA rated OSB, metal decking, etc.) for your metal roof system. The substrate must be on an even plane from eave to ridge to avoid panel distortion. The plane of the substrate should not vary more than 1/4" in 20 feet. SL1750 panel profile can be installed over spaced structural members; contact a CBM sales representative for details.

UNDERLAYMENT

Minimum underlayment recommendations consist of ASTM Type 30 felt (or equal), a non-asphalt fiberglass-based underlayment, or a high temperature self-adhering rubberized membrane. The underlayment used may depend on specific project conditions. Installation procedures shall be as recommended by underlayment manufacturer. Items to consider in the choice of underlayment are roof slope, panel profile, elevation (snow conditions), fire rating requirements, etc.

OIL CANNING

Flat metal panel surfaces will display some degree of waviness. This waviness is commonly referred to as "oil-canning". Oil canning is caused by a variety of conditions; steel mill tolerances, underlayments, variations in the substrate, and installation practices. Oil canning is a characteristic of metal roofing, and not a cause for rejection. CBM recommends using striations or stiffing ribs to help minimize or control the amount of oil canning.

SNOW DESIGN

The following details do not address certain snow conditions. Special consideration is needed when installing a metal roof system in heavy snow environments. Contact a CBM sales representative for details.

DELIVERY & STORAGE


Check shipment against shipping list. Report any damaged material to CBM immediately. Handle panels and bundles with care. Crated panels shall be lifted at blocked locations. Do not use ropes or wires for lifting. Long panels (25 ft. or more) may require two or more lift points to avoid bending or buckling of panels. Store panels in a dry, well ventilated area. Elevate one end of panels to allow for drainage of any moisture. Block panels off the ground. Do not store panels in direct contact with the ground. Do not allow strippable film to remain exposed to direct sunlight for an extended period of time. Remove strippable film prior to, or immediately after, installation of panels and flashing. Do not walk directly on standing seams. Wear shoes with non-marking soles.

GENERAL INSTALLATION INFORMATION

1. CBM recommends the use of a clutch / torque adjustable screw gun to properly install all fasteners referenced in this manual. Do not spin / strip any clip fasteners. Do not over torque or over drive any fasteners with neoprene washers.
2. If cutting is required, the panels must be cut with snips, shears or nibblers to prevent edge rusting. Do not use saws, abrasive blades, grinders or torches. All metal shavings (swarf) must be removed from panels and flashings immediately.
3. It is the responsibility of the installer to use safe construction practices and compliance with any and all state and Federal OSHA regulations.

CUSTOM-BILT METALS

Brand Products




DRAWING: SL 1 EAVE

All Flashing and Trim available through CBM	Note:
SUBJECT TO CHANGE WITHOUT NOTICE	

CUSTOM-BILT METALS

Brand Products



DRAWING: SL 2 EAVE / alternate


All Flashing and Trim available through CBM

SUBJECT TO CHANGE WITHOUT NOTICE

Note:

CUSTOM-BILT METALS

Brand Products



DRAWING: SL 4 EAVE w/ gutter


All Flashing and Trim available through CBM

Note:

SUBJECT TO CHANGE WITHOUT NOTICE

CUSTOM-BILT METALS

Brand Products




DRAWING: SL 5 EAVE w/ fascia

All Flashing and Trim available through CBM

SUBJECT TO CHANGE WITHOUT NOTICE

Note:




DRAWING: SL 6 RIDGE / HIP

All Flashing and Trim available through CBM	Note:
SUBJECT TO CHANGE WITHOUT NOTICE	

CUSTOM-BILT METALS

Brand Products



DRAWING: SL 7 VENTED RIDGE


All Flashing and Trim available through CBM

Note:

SUBJECT TO CHANGE WITHOUT NOTICE

CUSTOM-BILT METALS

Brand Products



DRAWING: SL 8 PEAK


All Flashing and Trim available through CBM

Note:

SUBJECT TO CHANGE WITHOUT NOTICE

CUSTOM-BILT METALS

Brand Products



DRAWING: SL 9 VALLEY thru-fastened


All Flashing and Trim available through CBM

Note: Use at roof slope under 3" in 12"

SUBJECT TO CHANGE WITHOUT NOTICE

CUSTOM-BILT METALS

Brand Products



DRAWING: SL 10 VALLEY cleat

All Flashing and Trim available through CBM




SUBJECT TO CHANGE WITHOUT NOTICE

Note: Dimensions may vary for Snow Conditions

CUSTOM-BILT METALS

Brand Products

RAKE SUPPORT TRIM



DRAWING: SL 11 RAKE

All Flashing and Trim available through CBM



SUBJECT TO CHANGE WITHOUT NOTICE

Note:


Effective Aug. 2011

CUSTOM-BILT METALS

Brand Products



RAKE SUPPORT TRIM




RAKE SIDEWALL FLASHING

DRAWING: SL 12 SIDEWALL

All Flashing and Trim available through CBM

SUBJECT TO CHANGE WITHOUT NOTICE

Note:



DRAWING: SL 13 HEADWALL


All Flashing and Trim available through CBM

SUBJECT TO CHANGE WITHOUT NOTICE

Note:

CUSTOM-BILT METALS

Brand Products



DRAWING: SL 14 HEADWALL


All Flashing and Trim available through CBM

SUBJECT TO CHANGE WITHOUT NOTICE

Note:

CUSTOM-BILT METALS

Brand Products




DRAWING: SL 15 HEADWALL- VENTED

All Flashing and Trim available through CBM

Note:

SUBJECT TO CHANGE WITHOUT NOTICE




DRAWING: SL 16 TRANSITION

All Flashing and Trim available through CBM


SUBJECT TO CHANGE WITHOUT NOTICE

Note:




DRAWING: SL 20 PIPE PENETRATION

All Flashing and Trim available through CBM	Note: Not to be used if size restricts water flow around panel
SUBJECT TO CHANGE WITHOUT NOTICE	




DRAWING: SL 22 EAVE / ISOMETRIC

All Flashing and Trim available through CBM	Note:
SUBJECT TO CHANGE WITHOUT NOTICE	



DRAWING: SL 23 VALLEY / ISOMETRIC

All Flashing and Trim available through CBM	Note:
SUBJECT TO CHANGE WITHOUT NOTICE	




DRAWING: SL 24 RIDGE / HIP ISOMETRIC

All Flashing and Trim available through CBM	Note:
SUBJECT TO CHANGE WITHOUT NOTICE	



ZEE CLOSURE

*Notch ZEE as shown and set in double bead tape
fasten through panel 1" in from sides and
4" on center
see expanded end view*




DRAWING: SL 25 ZEE CLOSURE / ISOMETRIC

All Flashing and Trim available through CBM

Note:


SUBJECT TO CHANGE WITHOUT NOTICE



NOT TO SCALE
SHOWN EXPANDED FOR CLARITY

DRAWING: SL 25a ZEE CLOSURE end view

All Flashing and Trim available through CBM	Note:
SUBJECT TO CHANGE WITHOUT NOTICE	



DRAWING: SL 26 CURB PENETRATION


All Flashing and Trim available through CBM

Note:

SUBJECT TO CHANGE WITHOUT NOTICE





Brand Products



DRAWING: SL 26a CURB PENETRATION / section

All Flashing and Trim available through CBM	Note:
SUBJECT TO CHANGE WITHOUT NOTICE	




DRAWING: SL 26b CURB PENETRATION / section

All Flashing and Trim available through CBM	Note:
SUBJECT TO CHANGE WITHOUT NOTICE	

CUSTOM-BILT METALS

Brand Products



DRAWING: SL 26c CURB PENETRATION / section


All Flashing and Trim available through CBM

Note:

SUBJECT TO CHANGE WITHOUT NOTICE

CUSTOM-BILT METALS

Brand Products














DRAWING: SL 27 PANEL LAP

All Flashing and Trim available through CBM

NOTE: NOT TO BE USED ON SLOPE UNDER 3:12







SUBJECT TO CHANGE WITHOUT NOTICE

Fastener Selection






Fastener	Description	USE
	#10 Pancake Screw Type A Zinc Plated Quadrex Drive	Metal to wood Clip or Trim to wood substrate
	#10 Pancake Screw Self-drill Zinc Plated Quadrex Drive	Metal to metal Clip or Trim to Metal substrate Min projection: 3/8" below substrate
	#10 Pancake Screw Type A Stainless Steel Quadrex Drive	Metal to wood Clip or Trim to wood substrate
	#12 Pancake Screw Self-drill Zinc Plated Quadrex Drive	Metal to metal Clip or Trim to Metal substrate
	#12 Pancake Screw Self-drill Stainless Steel	Metal to metal Clip or Trim to Metal substrate
	1/4-14 #2 Point 5/16" AF Zinc	Metal to metal Clip to Metal substrate
	Woodgrip/Painted #9-15 HWH Zinc Plated Sharp A Point w/washer 1/4" Hex Washer Head	Flashing / Trim to wood substrate
	Evergrip / Painted #9-15 HWH Stainless Steel Sharp A Point w/washer 1/4" Hex Washer Head	Flashing / Trim to wood substrate
	#12-14 Impax 5/16" Hex Washer Head SD2	Metal to metal Trim to Metal substrate
	1/4-14 X 7/8 Impax Lap 5/16" Hex Washer Head	Trim to Panel attachment Trim to Trim attachment Light gauge to Light gauge
	1/4-14 ZAC Lap (5/16") 5/16" AF Zinc Aluminum Capped Hex Washer Head	Trim to Panel attachment Trim to Trim attachment Light gauge to Light gauge

CUSTOM-BILT METALS

Brand Products


	12-14 ZAC (5/16") 5/16" AF Zinc Aluminum Capped Hex Washer Head	Flashing / Trim to Metal substrate
	10-15 HiLo WoodZac 5/16" AF Zinc Aluminum Capped Hex Washer Head	Flashing / Trim to wood substrate
	#14 Dekfast #3 Philips Head	Metal to metal Clip to Metal substrate Typical usage to attach panel clips through rigid insulation
	#14 Type A Mill Point 5/16" Hex Washer Head	Metal to Metal and Metal to Wood Recommende d for Contour 7/8 Roofing
	#12-14 Self-Drill STAINLESS Steel	Flashing / Trim to Metal substrate
	Blind Rivets Trim to Trim attachment	Stainless #43 1/8"Dia. Grip range .126 - .187 Stainless #44 1/8"Dia. Grip range .188 - .250 Aluminum #43 1/8"Dia. Grip range .126 - .187 Aluminum #44 1/8"Dia. Grip range .188 - .250 Available prefinished in standard colors

SEALANTS

SEALANT	Description	USE
 <p>3/16" BEAD</p>	<p>3/16" Bead Butyl Tape 25 foot rolls</p>	<p>Field applied seam sealant for concealed areas ONLY</p>
 <p>DOUBLE BEAD</p>	<p>7/8" Double Bead Butyl Tape 40 foot rolls</p> <p>3/4" Flat Butyl Tape 50 foot rolls</p>	<p>Per Recommended Details for concealed areas ONLY</p>
 <p>TRIPLE BEAD</p>	<p>2 1/2" Triple Bead Butyl Tape 20 foot rolls</p>	<p>Per Recommended Details for concealed areas ONLY</p>
	<p>10.5 oz. Cartridge-Non-Skinning Butyl Caulk</p>	<p>Gunnable caulk for concealed areas ONLY</p>
	<p>10.5 oz. Cartridge 1-component, polyurethane sealant</p>	<p>Gunnable caulk may be used in exposed areas</p>

PAINT

DESCRIPTION AND USE

	<p>DURANAR ADS PENS (air dry system) Touch Up paint for small / minor scratches in roofing material</p>
---	---

PIPE FLASHINGS



DEKTITE SIZE	FIT PIPE SIZES	Description
1	1/4" – 2"	Standard gray Temp range 212°
2	1 3/4" – 3 1/4"	Standard gray Temp range 212°
3	1/4" – 5"	Standard gray Temp range 212°
4	3" - 6 1/4"	Standard gray Temp range 212°
5	4 1/4" – 7 1/2"	Standard gray Temp range 212°
6	5" – 9"	Standard gray Temp range 212°
7	6" – 11"	Standard gray Temp range 212°
8	7" – 13"	Standard gray Temp range 212°
9	10" – 19"	Standard gray Temp range 212°

1	1/4" – 2"	High temp Red Temp range 437°
2	1 3/4" – 3 1/4"	High temp Red Temp range 437°
3	1/4" – 5"	High temp Red Temp range 437°
4	3" - 6 1/4"	High temp Red Temp range 437°
5	4 1/4" – 7 1/2"	High temp Red Temp range 437°
6	5" – 9"	High temp Red Temp range 437°
7	6" – 11"	High temp Red Temp range 437°
8	7" – 13"	High temp Red Temp range 437°
9	10" – 19"	High temp Red Temp range 437°



DEKTITE SIZE	FIT PIPE SIZES	Description
1	3/4" – 2 3/4"	Standard gray Temp range 212°
2	2" – 7 1/4"	Standard gray Temp range 212°
3	3 1/4" – 10"	Standard gray Temp range 212°

[illegible]



Corporate Headquarters
1333 Corporate Drive, Suite 103
Irving, TX 75038
(800) 826-7813
(972) 753-1111 Fax

Kent, WA
825 Central Ave. South
Kent, WA 98032
(253) 872-7330
(253) 395-7782 Fax
(800) 225-4682

Spokane, WA
812 North Madelia
Spokane, WA 99202
(509) 533-1703
(509) 533-1182 Fax
(800) 249-7372

Chino, CA
13950 Magnolia Ave.
Chino, CA 91710
(909) 664-1587
(909) 664-1577 Fax
(800) 886-2458

Sacramento, CA
4522 Parker Ave. Suite 400
McClellan, CA 95652
(916) 333-5680
(916) 640-1825 Fax
(800) 675-5111

San Jose, CA
121 Component Drive
San Jose, CA 95131
(408) 433-0823

Portland, OR
3250 NW Yeon Ave. Suite E-1
Portland, OR 97210
(503) 256-3328
(503) 256-4572 Fax
(800) 228-3143

Phoenix, AZ
115 Pioneer Street
Phoenix, AZ 85040
(602) 484-7015
(602) 484-0844 Fax
(800) 737-9030

New Orleans, LA
300 Jefferson Hwy.
Bldg. 11, Suite 1101
New Orleans, LA 70121
(504) 838-9344
(504) 838-9346 Fax
(800) 627-8040

Honolulu, HI
2312 Kamehameha Highway
Honolulu, HI 96819
(808) 845-1806
(808) 845-2702 Fax